BANGALORE BUILDINGS DIVISION, BANGALORE.

Notification dated 24th April 1933.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Bangalore Buildings Division, Bangalore up to 12th May 1933 (2 P.M.) for construtions of Sanskrit College Building, Bangalore. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of July 1935.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office, Buildings Division, Bangalore, between the hours of 11 A.M. and 5 P.M. on working days.

3. Tenders should be submitted on printed forms, which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the from given below, showing the rates at which the different items specified will be executed both in words and figures.

4. Each tender must be accompanied by a deposit of rupees two thousand only in cash or Government Promissory Notes, as earnest money and be superscribed "Tender for constructing a Building for Sanskrit College, Bangalore" in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Chief Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Percentage rates above or below the estimate rates will not be accepted.

10. No claims for enchanced rates will be entertained on any account after acceptance of tenders.

11. The contractor will be dealt with in terms of the bond for any short progress or delay. In matters of all disputes about rates, measurements, quality of work, etc., the decision of Chief Engineer will be final and legally binding over the contrators.

Abstract of estimate for constructing a building for Sanskrit College, Bangalore.

No.	Items of work	Unit	Quantity	Rates	
				In figures	In words
				Rs.	Rs.
1	Earth work excavation foundation and filling in basement including consolidation.	C.yd.	1,332		
2	Broken stone in lime mortar concrete for foundation in 4" layers.	C.ft.	12,006		
3	Burnt size stone in lime mortar with through bond stones for foundation and basement.	„	17,926		
4	Burnt stone slabs 6" thich over basement with chamferred edges, including one line dressing for exposed faces.	S.ft.	551		
5	Burnt stone slabs 6" thick one line dressed over interior walls of basement and cills and lintels of doors and windows.	„	1,314		
6	Superstucture—burnt brick in lime mortar ...	C.ft.	8,217		
7	Arch work—burnt brick in lime mortar ...	„	285		
8	Rolled steel beams and joists of Dorman Long or other approved make including lifting, hoisting and with a prime coat of approved paint.	Cwt.	228		
9	Roofing with jack arched tarrace as per specification in force.	Sqrs	33·00		

No.	Items of work	Unit	Quantity	Rates	
				In figures	In words
				Rs.	Rs
10.	Teak wood doors 3" x 5" frame work 1½" thick shutters, ⅓ panelled at bottom and 2/3 glazed at top, including brass fittings, brass rim, door locks, handles, etc, complete.	S.ft.	468		
11.	Teak wood windows 3" x 5" frame work 1¼" shutter ½ glazed at top and ½ panelled at bottom brass parliamentary hinges with brass hooks and rings, etc., complete.	,,	147		
12	Square cut stone pillars 12" at top and 15" at bottom with cap and base as per design.	C.ft.	213		
13	String course 6" x 3" with ornamental mouldings as per design.	R.ft.	116		
14	Reinforced cement concrete lovey cornice work with brackets and cement plastering, etc.	,,	16		
15	Plastering with lime mortar two coats and rendered smooth.	Sqr.	97 1/3		
16	White-washing two coats	,,	97 1/3		
17	Flooring with Mangalore tiles set in mortar concrete 3" bed and cement pointed nicely 9" Sqr.	,,	20		
18	Flooring with 1½" thich Cuddappah Slab on 3" concrete bed and pointed with cement.	,,	7		
19	Cement pointing to basement including raking joints ½" deep and nicely lined.	Sqr.	8 1/3		
20	Boxing girders with cement concrete including check block pipes, bolts and nuts and boring holes, plastering with cement.	C.ft.	161		
21	Charlton's Silicate painting two coats of approved colour.	Sqr.	12·50		
22	Teak wood stair case with stringers 3" thick and 12" deep 12" thread and 6" rise with 1¼" x 1" thick planks wrought and put up with bottom ceiling plank ¾" thick with all materials to fix including necessary brackets, etc., two coats of varnishing of approved make.	S.ft.	158		
23	Ornamental perforated parapet wall 3' high with base and coping as per design.	R.ft.	20		
24	Tie bars and clamps with bolts and nuts, etc., for Rolled Steel Joists.	Lump	sum Rs.		
	First Floor.				
1	Burnt brick in mortar for superstructure ..	C.ft.	6913		
2	Burnt stone slabs 6" thick one line dressed ...	S.ft.	386		
3	Teakwood doors 3½ x 5' frame work 1½" thick 1/3 panelled and 2/3 glazed shutters including brass fittings complete.	,,	468		
4	Teak wood windows 3" x 5" frame work 1¼' plank shutter half glazed ½ panelled with brass parliamentary hinges, hooks, rings, etc, complete.	,,	147		
5	Square pillars 12" top and 15" bottom of cut stone with base and cap as per design.	C.ft.	237		
6	Rolled Steel beams and joists of Dorman Long or other approved make with necessary clamps and nuts with a prime coat of approved paint lifting and hoisting, etc., complete.	Cwt.	197		

No.	Items of work	Unit	Quantity	Rates	
				In figures	In words
				Rs.	Rs.
7	Roofing with jack arch terracing as per specification in force.	Sqr.	34		
8	Flooring with Mangalore tiles set in mortar or granolithick flooring with coloured border and pointed with cement milky.	„	30½		
9	Archwork—brunt brick in lime mortar ...	C.ft.	201		
10	Plastering with lime mortar, two coats and rendered smooth.	Sqr.	79·00		
11	Whitewashing two coats ...	„	79·00		
12	Charlton silicate painting two coats ...	„	12·3		
13	Ornamental reinforced concrete lovey cornice work with brackets and cement plastering, etc., complete.	R.ft.	281		
14	Parapet (ornamental) wall 3' high with base and coping as per design.	„	235		
15	Reinforced concrete dome over the central portion.	Sqr.	6·3		
16	Finial over dome as per design ...	Lump	sum		
17	Ornamental features all round dome ...	Lump	sum		
18	Hand railing with top rail (teak wood) wrought iron ballustrades as per design with two coats varnishing and two coats of approved paint for ballustrades.	R.ft.	160		
19	Boxing griders with cement concrete including boring holes, check block pipes, etc., and plastering with cement.	C.ft.	138		
20	Tie bars, clamps, bolts and nuts for rolled steel joists.	Lump	sum		

A. TANDONI RAO,
Executive Engineer.

BANGALORE DIVISION.

Abstract Notification.

The attention of the public is invited to the notification inviting tenders up to 2 P.M. of 8th May 1933 for the Restoration of Channels from the Aralamallige tank in Dodballapur Taluk published on pages 434 and 435 of Part VI of the *Mysore Gazette*, dated 20th April 1933. The amount of earnest money to accompany the tender is Rs. 150.

ERRATUM.

In clause 1 of the notification, dated 7th April 1933 published on pages 434 and 435, Part VI of the *Mysore Gazette*, dated 20th April 1933 calling for tenders *for* "Restoring the channels from Aralamallige tank, Dodballapur Taluk" please *read* the date for receiving tenders as 8th May 1933 instead of 24th April 1933 as published, the other particulars remaining unaltered.

H. F. MARKER,
Executive Engineer,
6 G